MERCEDES-BENZ SPRINTER

BODY: 144 or 170

ROOF: High

DRIVE: 4WD or AWD

INTERIOR PACKAGE INCLUDES:

- Removable 3-Panel Bed System
- T-Vent windows
- Awning windows (170 wheelbase only)
- Powered venting
- Dimmable ceiling lights
- Wire passthroughs
- Insulation
- Infrastructure
- Sound damping
- Precision cut wall and ceiling panels
- Precision cut floor
- Fire extinguisher
- C02 detector
- Available fuse locations for future additions
- Dimmer relay
- Wheel well boxes

THE FINER DETAILS:

INFRASTRUCTURE

- Machine cut and folded 14 gauge and 16 gauge galvanized steel
- Strategically located wire passthroughs with safety grommets for ware protection

INSULATION AND SOUND DAMPENING

- Double-sided 3M Thinsulate packed into wall and ceiling cavities for thermal insulation
- Foil-wrapped butyl sound dampening added to the rear wheel wells for a more pleasurable driving experience

PRECISION CUT FLOOR

- 3/4-inch 11-ply marine grade plywood
- 1/8-inch foam thermal barrier
- Lonseal vinyl flooring
- Powder-coated aluminum stepwell trims

PRECISION CUT WALL PANELS

- 1/4-inch birch plywood
- Closed-cell foam backer
- Wrapped in interweave

3-PANEL BED SYSTEM

- · Powder-coated aluminum frame
- Precision-cut 3/8-inch light plywood wrapped with closed-cell foam and interweave
- Pre-installed bed rails securely fastened to the infrastructure for ultimate strength and durability

AFTERMARKET ADD-ONS

- 10-Speed Vent Fans (1x for the 144 wheelbase, 2x for the 170 wheelbase), wired to the chassis battery
- T-Vent Windows on the slider and driver side wall
- 10x33 Awning Windows (170 wheelbase only)
- Dimmable LED ceiling puck lights (8x for the 170 wheelbase, 6x for the 144 wheelbase) wired to the chassis battery
- Dimmer switches for ceiling lights pre-installed in the B and D pillars
- Fuse/Switch Box installed in the passenger seat base with 3 slots (20 amp max value)

QUALITY CONTROL

Before leaving the shop, our team of experts runs through a routine of checks on each van including:

- Leak testing in our state-of-the-art leak testing bay
- Component functionality
- · Fit and Finish checks

